















### Cross Sections of Works Requiring and Not Requiring Consents from SGC

Cross Sectional Diagram	Feature	Consent Required?
	Pipe Culvert (including extensions and removal)	Yes
	Oversized Box Culvert (including extensions and removal)	Yes
	Trash Screens	Yes
	Bank Protection Works	No – temporary works may require consent
	Pipe Crossing (in channel)	Yes
	Pipe Crossing (above bank)	No
	Pipe Crossing (below bed)	No – temporary works may require consent
	Protruding Pipe Out-Fall	No
	Outfall within Bank Profile	No
	Weir/Dam or impoundment or temporary works that obstruct flow	Yes
	Bridge (where soffit level is below bank top level)	Yes
	Bridge (abutments not reducing flow area/width)	No
	Clear Span Bridge	Yes
	Bridge with Support in Channel	No – the use of piers in the watercourse is discouraged